

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENCY'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 165-20034-0000 (of this well)

Operator's Full Name Frontier Oil Co.

Complete Address 1720 Kansas State Bank Bldg., Wichita, Kansas 67202

Lease Name McGill Well No. 4

Location C SW SE Sec. 3 Twp. 17 Rge. (E) (W) 17

County Rush Total Depth 3631'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by Allied Cementing Co.

Address Russell, Kansas License No.

Operation Completed: Hour 11 A Day 19 Month 12 Year 1977

The above well was plugged as follows:

Total Depth 3631' 8 5/8 csg set 200' cwc 135 sk.

4 1/2 csg set 3624' cw 275 sk cem. Perf. (3076'-3084')

DV tool set 1163' cwc 500 sk. No pipe recovered.

Allied Cementing Co. mixed & pumped down 4 1/2 csg with 35 sk cem. W/300 lbs hulls -
displaced with 20 sk gel & water & capped with cementing plug & 45 sk cem. & shutin.
SIP 100 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Lee Massey
Well Plugging Supervisor

10-020
12-21-77
6433-W

P