

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

NOV 8 1973

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Frontier Oil Company

Complete Address 1720 Wichita Plaza, Wichita, Kansas 67202

Lease Name Foos "B" Well No. 1

Location SE NE SE Sec. 16 Twp. 17 Rge. (E) (W) 17

County Rush Total Depth 3600'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11 :30 A Day 6 Month 11 Year 1973

The above well was plugged as follows:

Total Depth 3600' 8 5/8 csg set at 211' cwc 135 sk.

4 1/2 csg set at 3598' cw 275 sk cem.

4 1/2 csg perf. (3059-3591)

Set 4 1/2 wood plug at 3000' -- poured 25' sd & dumped 3 sk cem W/dump bailer. (2935-3000)

Cutoff and recovered 2100' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -- released 8 5/8 plug

and pumped 120 sk 50-50 poz cem W/2 % total gel. Max PP 350# SIP 150#

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Mussy
Well Plugging Supervisor

11/9/73
INV. NO. 8141-W