

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas
(of this well)

API Number 15 -165-19017-0000

Operator's Full Name Frontier Oil Co.
Complete Address 1720 Kansas State Bank Bldg., Wichita, Kansas 67202
Lease Name Kaiser Well No. 1
Location SW SW NE Sec. 2 Twp. 17 Rge. (E) (W) 17
County Rush Total Depth 3657'
Abandoned Oil Well Gas Well XX Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co. tools by Allied Cementing Co.
Address Same as above License No.
Operation Completed: Hour 10:10 A Day 17 Month 8 Year 1978

The above well was plugged as follows:

Total Depth 3657' 8 5/8 csg set 212' cwc 125 sk.
4 1/2 csg set 3219' cw 250 sk cem. PFS (3058'-3066')
4 1/2 csg DV tool set 1175' cwc 550 sk. No pipe recovered.
Mixed & pumped down 4 1/2 csg with 50 sk 50-50 poz 2% -3 hulls -displaced with 25 sk
gel & water -repeased plug & capped with 40 sk 50-50 poz 2% & shutin. Mpp 1000 lbs
SIP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 8-18-78
7883-W