

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 26 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Bovaird Supply Co.

Complete Address: Box 358, Liberal, Kansas

Lease Name Daisy Wall Well No. 1

*(CNESE) Not SA E of NW (CSW NW)*  
Location 1980' of 1/4 of 1/4 & 660' of 1/4 of 1/4 Sec. 35 Twp. 32 Rge. 23 (E) (W)

County Clark Total Depth 6859'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 3:00PM Day 19 Month 8 Year 1968

The Above well was plugged as follows:

13 3/8" to 525' circulated w/ cement. 9 5/8" to 2510' circulated w/ cement.

5 1/2" to 6818' cemented. Top perforations 44760.

Plug bottom w/ 15 sacks cement Top of cement 4300'

Mud 4300' to 700' #0 Spotted 40 sacks cement 700' to 600'

Mud 600' to 45' Plug, Halls & 15 sacks cement 45' to 0'

Company Pump Pulled 2817' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INDEXED  
DATE 8/26/68  
INDEX NO. 8339-W

Signed: *Edgar J. Ede*  
Well Plugging Supervisor