

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Shell Oil Co.

Complete Address: P. O. Box 744 Great Bend, Kansas

Lease Name P. A. Brown "B" Well No. 1-23

Location C NE SW Sec. 23 Twp. 25 Rge. 34W (~~EX~~) (W)

County Finney Total Depth 5282'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Helmerich & Payne Inc.

Address: First Nat'l Bldg. Tulsa, Oklahoma License No.     

Operation Completed: Hour      Day 16 Month July Year 1959

The Above well was plugged as follows:

<u>Hole full of heavy rotary mud. Ran drillpipe in hole.</u>	
<u>mixed &amp; pumped 150 sx Portland cement down hole leaving</u>	
<u>cement plugs 2800-2500-(120 sax), 850-769 (25 sax) &amp;</u>	
<u>25-0 (5 sax).</u>	<u>5282-2800 Mud</u>
	<u>2800-2500 Cement</u>
	<u>2500-850 Mud</u>
	<u>850-769 Cement</u>
	<u>769-25 Mud</u>
	<u>25-0 Cement</u>

I hereby certify that the above well was plugged as herein stated. W. L. Leckamp

Signed: W. L. Leckamp  
Well Plugging Supervisor

*W. L. Leckamp*