

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22922-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 28-32S-10W  
364 feet from S Section Line, 1661 feet from E Section Line  
Lease Name: TRANHAM MCGUIRE Well #: 2  
County: BARBER Total Vertical Depth: 4737 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 124 N MAIN PO BOX 195  
ATTICA, KS 67009

| String | Size  | Depth (ft) | Pulled (ft) | Comment         |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 4770       |             | WITH 2 SX CMT   |
| PROD   | 5.5   | 4730       | 3492        | WITH 125 SX CMT |
| SURF   | 8.625 | 220        |             | WITH 210 SX CMT |

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2013 9:00 AM  
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.  
Proposal Rcvd. from: JEFF CAPPS Company: SHAWNEE WELL SERVICE, INC. Phone: (620) 254-7893

Proposed Plugging Method: SET CIBP @ 4780' WITH 2 SX CMT. PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. PLUG AT 220' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/06/2013 9:55 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4770' WITH 2 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 260' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4430 | 4470 |      |          |

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA

MAY 22 2013

RECEIVED

District: 01

RECEIVED

MAY 16 2013

KCC DODGE CITY

Signed

*Michael Maier*  
6/06/13

(TECHNICIAN)