

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-055-225350000 ²¹⁵³⁵⁻⁰⁰⁰⁰

LEASE NAME Bruegel

WELL NUMBER 1-20

4950 Ft. from S Section Line

500 Ft. from E Section Line

SEC. 20 TWP. 25S RGE. 34 (E) or (W)

COUNTY Finney

Date Well Completed 3-24-97

Plugging Commenced 3-24-97

Plugging Completed 3-24-97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS 2606 Fleming Garden City, Kansas 67846

PHONE# (316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well P&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-21-97 (date)

by Dodge City KSCC (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation None Depth to Top _____ Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled
		0	1900	8 5/8	1900	0

RECEIVED
 KANSAS CORP COM
 1997 MAR 27 A 11 48 AM

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from _____ feet to _____ feet each s. All cmt. is 60/40 Poz H. 1st plug w/100 sks from 3070 to 2600'. 2nd plug w/50 sks from 1930' to 1660'. 3rd plug w/40 sks from 880' to 670'. 4th plug w/10 sks from 40' to 0'. 15 sks in rathole and 10 sks in mousehole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address Liberal, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.

STATE OF Kansas COUNTY OF Finney, ss.

Ken Jehlik (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) Ken Jehlik

(Address) 2606 Fleming, Garden City, KS

SUBSCRIBED AND SWORN TO before me this 26 day of March, 19 97

John F. Richner
 Notary Public

My Commission Expires: August 15, 2000