


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Finney County, Sec. 23 Twp. 25S Rge. (E) 34(W)

Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Shell Oil Company
Lease Name P. A. Brown "B" Well No. 1-23
Office Address Post Office Box 744, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 16 19 59
Application for plugging filed July 21 19 59
Application for plugging approved (Verbal) July 16 19 59
Plugging commenced July 16 19 59
Plugging completed July 16 19 59
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation Mississippian Depth to top _____ Bottom _____ Total Depth of Well 5282 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole full of heavy rotary mud. Ran drill pipe in hole, mixed & pumped 150 sax Portland cement down hole leaving cement plugs 2800-2500 (120 sax), 850-769 (25 sax) & 25-0 (5 sax).

5282-2800 Mud
2800-2500 Cement
2500-850 Mud
850-769 Cement
769-25 Mud
25-0 Cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Helmerich & Payne, Inc.
Address First National Building, Tulsa, Oklahoma

STATE OF Kansas COUNTY OF Barton, ss.
A. W. Weber (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A W Weber
P. O. Box 744, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 19 59

Salmon Byers, Jr
Notary Public.

My commission expires January 28, 1961

PLUGGING
FILE SEC 231 25 R 344
BOOK PAGE 52 LINE 45

SHELL-P. A. BROWN "B" NO. 1-23
C NE SW Section 23-25S-34W
WILDCAT, HUGOTON FIELD (AREA 2)
FINNEY COUNTY, KANSAS

Casing Record

8 5/8" cem 848 with 650 sax; cem. circ.

- 0 - 534 surface, sandy
- 863 sand & red bed
- 983 red bed, sand, shells & shale
- 1525 red bed & sand
- 2145 lime & shale
- 2438 shale
- 2510 lime & shale
- 2785 shale
- 2945 lime & shale
- 3015 shale & lime
- 3220 lime & shale
- 3551 shale
- 3646 shale & chalk
- 3798 chalk & shale
- 3858 shale
- 3948 lime & shale
- 4224 lime
- 4280 lime & shale
- 4351 sand & lime
- 4630 lime & shale
- 4664 lime
- 4808 lime & shale
- 4848 lime
- 4965 lime & shale
- 5284 lime
- 5284=5282.83 SLC
- 5282 T.D.

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Shell-P. A. Brown "B" Area 2 No. 1-23 well, located in Section 23-25S-34W, Finney County, Kansas.

SHELL OIL COMPANY
by A. W. Weber
District Superintendent

Subscribed and sworn to before me a Notary Public this 22nd day of July, 1959.
My commission expires January 28, 1961 L. Mont Byers Jr., Notary Public

PLUGGING
FILE SEC. 23 T. 25 R. 34W
BOOK PAGE 52 LINE 45