

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

10			

Locate well correctly on above
Section Plat

Finney, _____ County. Sec. 7 Twp. 25 Rge. 34W ~~48E~~ (W)

Location as "NE/CNW/SW" or footage from lines C SE SE

Lease Owner Helmerich & Payne, Inc.

Lease Name Wagner "A" Well No. 1

Office Address Box 558 Garden City, Kansas 67846

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19____

Application for plugging filed _____ 19__

Application for plugging approved _____ 19____

Plugging commenced _____ May 31 1967

Plugging completed June 6 1967

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well **5172** Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mixed 15 sks. cement and 1 sk. hulls to plug off perforations.
Stop plug at 4,000'. Shot pipe at 3,958' and worked same
loose; lay down 93 jnts. Lay down casing to 700' and spot
40 sks. cement at 700' to 600'. Lay down all casing (125 jnts. in all)

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1967

~~CONSERVATION DIVISION~~
~~Wichita, Kansas~~

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor. Sargent's Casing Pulling Service

Address Box 506, Liberal, Kansas 67901

STATE OF KANSAS, COUNTY OF SEWARD, ss.

Robert Sargent (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert J. [unclear]

Liberal, Kansas 67901

(Address)

Sworn to before me this 7th day of June, 1967

DeAnn Corbin Notary Public

My Commission expires Jan. 16, 1970

Notary Public.



WAGNER "A" WELL NO. 1

C SE SE
SECTION 7-25S-34W
FINNEY COUNTY, KANSAS

CONTRACTOR: RINE DRILLING COMPANY, INC.

STARTED: MAY 2, 1967

COMPLETED: MAY 13, 1967

L O G

Sand	0'	-	450'
Red Bed	450'	-	850'
Red Bed, Anhydrite, & Sand	850'	-	2010'
Anhydrite	2010'	-	2380'
Lime Streaks	2380'	-	2685'
Lime	2685'	-	2965'
Lime Streaks	2965'	-	3240'
Shale	3240'	-	3427'
Lime Streaks	3427'	-	3580'
Lime Streaks & Shale	3580'	-	3785'
Lime	3785'	-	3905'
Lime & Shale	3905'	-	4047'
Lime	4047'	-	4275'
Lime Streaks	4275'	-	4415'
Lime	4415'	-	4625'
Lime Streaks	4625'	-	4725'
Lime	4725'	-	4791'
Lime & Shale	4791'	-	4920'
Lime Streaks	4920'	-	4985'
Lime	4985'	-	5140'
Lime Streaks	5140'	-	5174'

totco - 1/2° @ 500'; 1/2° @ 816'
Ran 38 jts. 24# casing to 816'. Cem. w/350
sx. poz 2% c.c. & 150 sx. common 3% c.c.
Totco - 1/2° @ 2199'

Totco - 1° @ 2930'

Totco - 3/4° @ 3790'

Totco - 1° @ 4222'

Totco - 1/4° @ 5100'
Ran 164 jts. 14# J-55 Csg. to 5174'
Cem w/250 sx. poz salt sat.

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1967
CONSERVATION DIVISION
Wichita, Kansas


STATE OF KANSAS)
COUNTY OF SEDGWICK)

ss

I, R. M. Green, do certify that the above is a true and accurate log of the Wagner "A" Well No. 1, located C of SE of SE of Section 7-25S-34W, Finney County, Kansas.


R. M. Green, Secretary-Treasurer

Subscribed and sworn to before me this 19th day of May, 1967.


Sam R. Clift, Notary Public

My Commission Expires: 9/4/68