


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Finney

County. Sec. 19 Twp. 24S Rge. (E) 33 (W)

Location as "NE/CNW/SW" or footage from lines C NW/4 NW/4

Lease Owner Greenland Drilling Company

Lease Name SERATT "A"

Well No. 2

Office Address 4722 Broadway, Kansas City 12, Mo.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-2 19 59

Application for plugging filed 10-2 19 59

Application for plugging approved 10-2 19 59

Plugging commenced 10-2 19 59

Plugging completed 10-2 19 59

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation Depth to top Bottom Total Depth of Well 5057 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	610'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

120 sacks cement through drill pipe @ 2820'

Plug and 20 sacks cement @ 600'

Plug and 10 sacks cement @ 35'

RECEIVED

STATE CORPORATION COMMISSION

OCT 12 1959

CONSERVATION DIVISION

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Greenland Drilling Company

Address 4722 Broadway, Kansas City 12, Mo.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Oscar Bridge, Vice-President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Oscar Bridge, Vice-President Greenland Drilling Co.
4722 Broadway, Kansas City 12, Mo.
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1959

Verdina B. Antledge

Notary Public.

My commission expires 3-15-60

WELL LOG

Company: GREENLAND DRILLING COMPANY

Sec. 19 Twp. 24S Rge. 33W

Farm: SPRATT "A" No. 2

Location: C NW NW

Finney County, Kansas

Commenced: 9-11-59

Completed: 10- 2-59

Total Depth: 5057

Contractor: GREENLAND DRILLING COMPANY

Casing: 8-5/8" 610'
5-1/2" ----

Elevation: 2941 RB

Production: D & A

Figures Indicate Bottom of Formations

180	Sand	TOPS: (Schlumberger)	
420	Shale & sand	Herrington	2537
610	Shale	Upper Krider	2570
655	Shale & shells	Lower Krider	2587
670	Shale & sandy shale	Winfield	2621
730	Shale	Upper Ft. Riley	2685
775	Sandy shale	Lower Ft. Riley	2752
795	Shale	Council Grove	2876
1150	Shale & lime	Heebner	3902
1335	Shale & shells	Toronto	3916
1375	Shale & sand	Lansing	3994
1400	Shale, shells & pyrite	Marmaton	4488
1470	Lime & shale	Cherokee	4602
1850	Sand & Red Bed	Morrow	4843
2050	Lime	St. Gen.	4948
2395	Shale & lime	St. Louis	4956
2545	Lime	RTD	5057
2649	Shale & lime		
2775	Sand	DRILL STEM TESTS:	
2845	Lime & sand streaks	3141-3301	
2923	Lime & shale	Open 1 hr. closed 20 min.	
3052	Lime	120' muddy salt water	
3123	Lime & shale	BHP 735#	
3260	Lime		
3307	Lime, sand & shale	4330-4405	
3450	Lime	Open 1 hr. closed 20 min.	
3617	Lime & shale	1350' salt water	
3703	Lime, shale & sand	BHP 1225#	
3783	Lime & shale		
3798	Lime	4855-4990	
3875	Lime & shale	Weak blow 41 min. died.	
3947	Lime	10' mud	
4405	Lime	BHP 133#	
4513	Lime & shale		
4600	Lime	5022-5057	
4703	Lime & shale	Open 1 hr. closed 20 min.	
4849	Lime	700' gassy cut salt water	
4865	Shale, lime & sand	BHP 1273#	
4933	Shale & lime		
4990	Lime		
5057	Miss.		
5057	RTD.		

STATE OF KANSAS, COUNTY OF SEDGWICK, SS:

I, Oscar Bridge, of the Greenland Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the #2 SPRATT "A" well.

Oscar Bridge
Oscar Bridge, Vice-President

Subscribed and sworn to before me this 9th day of October, 1959.

Verdina B. Rutledge
Verdina B. Rutledge, Notary Public

My commission expires March 15, 1960.