

15-165-19015-0000

API NUMBER 7-30-64

LEASE NAME Grout

WELL NUMBER #1

SPOT LOCATION C SW/4

SEC. 9 TWP. 17 SRGE. 17 ~~(E)~~ or (W)

COUNTY Rush

Date Well Completed 7-30-64

Plugging Commenced 4-20-90

Plugging Completed 4-20-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR AFG Energy, Inc.

ADDRESS P.O. Box 605, Russell, KS 67665

PHONE # (913) 483-6213 OPERATORS LICENSE NO. 3456

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Topeka Depth to top 3064 bottom 3296 T.D. 3190' PBTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka	Gas	3064	3296	8 5/8"	135'	None
				4 1/2"	3609'	None

DV at 1193'-550 sx.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped down 4 1/2" casing - mixed 300# hulls - 50 sx. common cement - 250 sxs. 60/40 Poz, 6% gel. Pressured to 1200# SI at 600#. Hooked to 8 5/8" and pumped 12 sx. 60/40 Poz, 6% gel. 500# solid.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_  
Address Russell, KS

STATE OF Kansas COUNTY OF Russell, ss.

Terry W. Piekser (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piekser

(Address) P.O. Box 605, Russell, KS



SUBSCRIBED AND SWORN TO before me this 15th day of May, 1990

Pamela K. Steckel  
Notary Public

My Commission expires: 11-19-92