

6-17 15.001.05322.00.00

3021344

TO:

API NUMBER 15-

STATE CORPORATION COMMISSION

SW , SEC. 18 , T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

3490 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BARNETT WELL # M

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE #

WELL TOTAL DEPTH 910' FEET

OPERATOR: STATE OF KANSAS

CONDUCTOR PIPE: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 7 FEET N/A

ADDRESS

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD WELL ☐ D/A ☐

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SPLANE PULLING AND ROUSTABOUT SERVICE LICENSE NUMBER 6372

ADDRESS P.O. BOX 386, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 10:30AM DAY: 17 MONTH: 6 YEAR: 97

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 900' THAT HAD BEEN

CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 4 1/2"

CASING FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL ☒ PART ☐ NONE ☐

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 17 MONTH: 6 YEAR: 97

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 900'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 1" AND 4 1/2" ANNULUS AT

SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE.

90 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

REMARKS: Control # 19970160-026

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3

RECEIVED
KANSAS CORP COM
1997 AUG 26 4 11:57 PM