

3021348

6-26

15.001.03327.00.00

TO:

API NUMBER 15-

STATE CORPORATION COMMISSION

SW , SEC. 18 , T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

635 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

3795 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BARNETT WELL # 16-B

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE #

WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS

CONDUCTOR PIPE: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 10 FEET N/A

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SPLANE PULLING AND ROUSTABOUT SERVICE LICENSE NUMBER 6372

ADDRESS P.O. BOX 386, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 8:00AM DAY: 26 MONTH: 6 YEAR: 97

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: VISIBLE AT SURFACE ON THIS WELL WAS 10" SURFACE CASING ONLY. SOLID CEMENT
WAS ENCOUNTERED INSIDE THE 10" AT 77'. THE WELL HAD EVIDENTLY BEEN PLUGGED IN THE
PAST. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE WELL FULL OF CEMENT FROM 77' TO
SURFACE.

PLUGGING PROPOSAL RECEIVED BY STEVE KORF

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 26 MONTH: 6 YEAR: 97

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE 10" SURFACE CASING TO 77'. CEMENT
WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 1" AND 10" ANNULUS AT
SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE.
42 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

REMARKS: Control #19970160-013

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3

RECEIVED
KANSAS CORP COM
NOV 26 4 11 56 PM '97