

3021355

7-17

15.001.03328.00.00

TO:

API NUMBER 15-

STATE CORPORATION COMMISSION

SW , SEC. 18 , T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

1430 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

3600 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BARNETT WELL # 0

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE #

WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS

CONDUCTOR PIPE: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 7 FEET N/A

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SPLANE PULLING AND ROUSTABOUT SERVICE LICENSE NUMBER 6372

ADDRESS P.O. BOX 386, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 2:00PM DAY: 17 MONTH: 7 YEAR: 97

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: THIS WELL CONSISTED OF 2 1/2" CASING TO APPROXIMATELY 800' THAT HAD BEEN
CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2 1/2"
CASING FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 17 MONTH: 7 YEAR: 97

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE 2 1/2" CASING TO 800', CEMENT WAS
PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 1" AND 2 1/2" ANNULUS AT
SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM
SURFACE. 35 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

REMARKS: Control # 19970160-031

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-2/3

RECEIVED
KANSAS CORP COM
AUG 26 1997