

3021345

6-18

15.001.03333.00.00

TO:

API NUMBER 15-

STATE CORPORATION COMMISSION

SW , SEC. 18 , T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

520 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

3715 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BARNETT WELL # 21

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE #

WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS

CONDUCTOR PIPE: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 10 FEET N/A

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SPLANE PULLING AND ROUSTABOUT SERVICE LICENSE NUMBER 6372

ADDRESS P.O. BOX 386, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 2:30PM DAY: 18 MONTH: 6 YEAR: 97

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: THIS WELL CONSISTED OF 1 1/2" CASING TO APPROXIMATELY 800' THAT HAD BEEN
CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL
AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE 1 1/2" CASING.

PLUGGING PROPOSAL RECEIVED BY STEVE KORF

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:15 PM DAY: 18 MONTH: 6 YEAR: 97

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN INTO THE 1 1/2" CASING TO 750'. 1" PIPE

WAS RAN INTO THE 1 1/2" AND 10" ANNULUS TO 700'. CEMENT WAS PUMPED INTO THE 3/4" PIPE

UNTIL CEMENT CIRCULATED FROM THE 3/4" AND 1 1/2" ANNULUS AT SURFACE. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 1 1/2" AND 10" ANNULUS AT

SURFACE. BOTH THE 3/4" AND 1" PIPE WERE REMOVED. SETTLAGE AND DISPLACEMENT WERE

FILLED FROM SURFACE. 269 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

REMARKS: Control #19970100-015

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXX) OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM TP-2/3

RECEIVED
KANSAS CORPORATION
1997 MAR 26 AM 10:26