

3021677

TO:

15-001-01068-00-00
 API NUMBER 15- CONTROL #20000019001
 NW, SEC. 5, T 25 S, R 19 (Per Ab. Well Database)

STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION 4670 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4290 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME FREIMILLER WELL # FRE01

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE #

WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS

PRODUCTION CSG: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 8" FEET N/A

ADDRESS

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR K.W. OIL WELL SERVICES, INC. LICENSE NUMBER 3097

ADDRESS 19450 FORD ROAD, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 8:00AM DAY: 21 MONTH: 9 YEAR: 99

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-432-2300

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED

IN FROM TD TO APPROXIMATELY 400'. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF

THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE 2" CASING.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:00AM DAY: 21 MONTH: 9 YEAR: 99

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE 2" CASING TO 800'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 400'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. CEMENT WAS PUMPED BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
 (TECHNICIAN)

