

API Well Number: 15-121-02353-0000

Kansas Corporation Commission

District Plugging Report

Spot: SWSW Sec 28 Twp 16 S Rng 24 E / W
175 Feet from N / S Line of Section
5193 Feet from E / W Line of Section
GPS: Lat: 38.621739 Long: 94.76855 Date: 10/19/10
Lease Name: BAUM (GRIMES) Well #: BAU 01
County: Miami Total Vertical Depth: 398 feet

Operator License No: 101 String Size Depth Pulled Comments
Op Name: STATE OF KANSAS COND - Conductor Pipe 7,000 20 0 EST.
Address 1: 130 S. MARKET PROD - Casing 2,000 398 0
Address 2: _____
City: WICHITA _____
State: KS Zip Code: 67202 - _____

Well Type: OG - Oil & Gas UIC Docket No.: _____ Date/Time to Plug: 4/21/11 / 10:00 am
Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
Proposal Revd from: JEFF FREDRICKS Company Name: SAME Phone: (620) 431-8945

PUMP CEMENT FROM TD TO SURFACE INSIDE AND OUTSIDE OF 2".

Proposed
Plugging
Report:

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: PART - Partial
Date/Time Plugging Completed: 4/21/11 / 1:30 pm KCC Agent: FRANK GUILFOYLE
Actual Plugging Report:


WASH 1" DOWN INSIDE 2" TO 398 FT. WASH 1" DOWN OUTSIDE OF 2" TO 270 FT. PUMP PORTLAND CEMENT FROM TD TO SURFACE INSIDE AND OUTSIDE OF 2". PULL PIPE AND TOP OFF WELL. DIG DOWN AND CUT OFF WELL. EMPTY PIT. BACKFILL PIT AND LEVEL OUT AREA. PUMP TOTAL OF 89 SACKS OF CEMENT. WELL PLUGGED.

KANSAS CORPORATION COMMISSION
JUL 28 2011
RECEIVED

Remarks: CONTROL NUMBER 20110068-001. PURCHASE ORDER # 14300-0000000667. REG. SEC.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03


(Francis J. Guilfoyle)
Form: District Plugging Report - _____