

3 020601

8-2

114 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 001-20,835 -0000
NW, SEC. 18, T26 S, R18 N/E

5080 feet from S section line
4880 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5490

Lease Name C. Johnson Well # N-15

Operator: Wimsett Oil Inc.

County Allen 25.00

Name & Address R.R. #2, Box 98

Well Total Depth 736 feet

Chanute, Kansas 66720

Conductor Pipe: Size feet

Surface Casing: Size 6 1/4 feet 20

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Consolidated Oil Well Services Inc. License Number 4996

Address 211 W. 14th Street, Chanute, Kansas 66720

Company to plug at: Hour: 11:00 am Day: 2 Month: 8 Year: 19 89

Plugging proposal received from Mike Wimsett

(company name) Wimsett Oil Co. Inc. (phone) 316-431-4137

were: This well consisted of 2" casing to approximately 736' that had been
cemented in from bottom to top. The plugging proposal was to squeeze the
2" casing full of cement from surface.

STATE CORPORATION COMMISSION
SEP 27 1989
CONSERVATION DIVISION

Plugging Proposal Received by Clayton P. Titel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 am Day: 2 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT The pump truck was connected directly to the 2" casing.
Cottonseed hulls were mixed with the first of the cement to be pumped
into the well. Cement was pumped into the well until it pressured up.
The well was shut in at 1000 PSI. 18 sacks of cement were pumped into
this well by Consolidated Oil Well Services Inc.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

(XXX) did not observe this plugging.

DATE 10-9-89

Signed Clayton P. Titel (TECHNICIAN)

INV. NO. 26040