

3 021785

15-001-01132-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 30345

Operator: PIQUA PETROLEUM, INC.

Name & ROUTE 1

Address PIQUA, KS 66761

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE

Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KS 66720

Company to plug at: Hour: 2:00 PM Day: 8 Month: 2 2000

Plugging proposal received from: MIKE KEPLEY

Company Name: KEPLEY WELL SERVICE Phone: 316-431-9212

Were: THIS WELL CONSISTED OF 6" CASING TO APPROXIMATELY 800' THAT HAD BEEN

CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO PERFORATE THE CASING

AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

C.P. TITEL

Plugging attended by Agent: All ☒ Part ☐

TECHNICIAN

None ☐

Operations Completed: Hour: 5:00 PM Day: 8 Month: 2 2000

Actual Plugging Report: THE 6" CASING WAS PERFORATED AT 500' AND AT 200'. 1" PIPE

WAS RAN INTO THE 6" CASING TO 725'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT

CIRCULATED FROM THE 6" CASING AND FROM THE 6" AND 8" ANNULUS AT SURFACE.

THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED

STATE CORPORATION COMMISSION

FEB 22 2000

Remarks:

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

I DID

observe this plugging.

INVOICED

DATE 3/3/00

INV. NO. 061387

Signed:

Clayton P. Titel
TECHNICIAN

(R)