

15.001.03357.00.00
2-12 83 R

3 020631

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Old Hole
SW , SEC. 18, T 26 S, R 18 W/E
2093 feet from S section line
4415 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3602

Lease Name Barnett Well # B
County Allen 35.00

Operator: Aspen Oil & Gas Co.
Name &
Address 10288 W. Chatfield, Suite 102

Well Total Depth Approx. 800 feet

Idyllarion, CO 80127
P.O. Box 598
Chanute, KS
66720

Conductor Pipe: Size feet

Surface Casing: Size 7" feet

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Heat Can License Number 30293

Address P.O. Box 223, Chanute, Kansas 66720

Company to plug at: Hour: 2:00 pm Day: 29 Month: 1 Year: 19 90

Plugging proposal received from H.T. Laidlaw

(company name) Aspen Oil & Gas Co. (phone) 303-973-2555

were: This well consisted of 1 1/2" casing to approximately 800' that had been cemented in at TD only. 3/4" tubing on a packer was probably to near TD inside the 1 1/2" casing. The plugging proposal was to remove as much of the 3/4" tubing as possible and circulate as much of the well as possible full of cement.

Plugging Proposal Received by Clayton P. Titel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:00 pm Day: 12 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT 462' of 3/4" pipe were fished from inside the 1 1/2" casing.

1/2" pipe was ran to 462' inside the 1 1/2" casing. 1" pipe was ran to 725' in the 1 1/2" and 7" annulus. Cement was pumped into the 1" pipe until cement circulated from the 1 1/2" and 7" annulus at surface. 10 sacks of cement were then pumped into the 1/2" pipe. The 1" pipe and 1/2" pipe were both then removed.

Displacement and settlage were filled from surface. An estimated 160 sacks of

Remarks: cement were pumped into this well by Consolidated Oil Well Services, Inc.
(additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 4-26-90

Signed Clayton P. Titel
(TECHNICIAN)

INV. NO. 27977

MAY 24 1990