

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20757-00-00  
Spot: W2NWSE Sec/Twnshp/Rge: 4-27S-6W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: KING Well #: 1  
County: KINGMAN Total Vertical Depth: 4130 feet

Operator License No.: 104  
Op Name: KANSAS CORPORATION COMMISSION  
Address: 130 S MARKET RM 2078  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	332		150 SXS CMT
PROD	4.5	3775		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/19/2010 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: \_\_\_\_\_

Proposed Plugging Method: SAND BACK THE PERFS TO 3675 AND CAP WITH 4 SKS OF CMT. PERFORATE AT 950', 35 SKS AT 450', AND CIRC CMT TO SURFACE FROM 382'.

Plugging Proposal Received By: B. J. HOPE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/22/2010 1:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

GAS WOULD NOT BLOW DOWN. TIED ONTO THE CASING AND PUMPED 35 SKS OF 3% CACL CMT, DISPLACED TO 3200'. LEFT SHUT IN OVER NITE. TAGGED CMT THE NEXT DAY AT 3000'. PERFORATED THE CASING AT 950, SPOTTED 35 SKS OF CMT. PERFORATED CASING AT 400'. RAN TUBING TO 400' AND FILLED CASING. TIED ONTO 4.5 CASING AND PUMPED 85 SKS OF CMT. CMT DID CIRCULATE UP THE BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
3724	3726	CSG	

Control # 20110042-001

RECEIVED  
APR 11 2011  
KCC WICHITA

Remarks: QUALITY WELL SERVICE

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)