

15-133-19440-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER _____
NE,NW,SE _____ Sec/Twp/Rge 34-28-20 E
2026 feet from south section line
1432 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # NIA 101 *JUL 0.3 2002*

Operator: State of Kansas *KCC WICHITA*

Name & KCC

Address _____

AB oil well Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Splane Pulling & Roustabout Service Inc. Lic. # 6372

Address: P. O. Box 386, Chanute, Ks 66720

Company to plug at: Hour: 10:00 Day: _____ Month: 6 2002

Plugging proposal received from: KCC District Staff

Company Name: KCC Phone: 316-432-2300

Were: Wash down inside and outside of 2" to TD, run plugging string to 450 ft circulate cement from bottom to top inside and out. Pull plugging string and top off well.

Plugging Proposal Received by: Troy A. Russell

Plugging attended by Agent: All Part _____
TECHNICIAN
None _____

Operations Completed: Hour: 11:30 Day: _____ Month: 6 2002

Actual Plugging Report: Washed down to 450 ft inside 2". Washed down approximately 25 ft outside. The well was then perforated at a depth of 200 ft and 75 ft by Jim Comish. 450 ft of 3/4" was then washed down the 2". Approximately 3 to 4 barrels of water was used to pump approximate 20 sacks of cement down the 2". The plugging string was then pulled and approximately 25 ft of 1" ran down the outside and approximately 2 to 3 barrels of water used to circulate cement.
Contractor calculated 20 sacks of cement for this well.

Remarks: Control # 20020063-006
(if additional description is necessary, use BACK of this form.)

I did observe this plugging.

Signed: Troy A. Russell
TECHNICIAN

ll
OK