

3021300

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
WICHITA STATE OFFICE BLDG., 130 S. MARKET
WICHITA, KANSAS 67202
TECHNICIAN'S PLUGGING REPORT
OPERATOR LICENSE # _____
OPERATOR: STATE OF KANSAS
NAME AND FEE FUND PLUGGING
ADDRESS _____
ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____
OTHER WELL AS HEREINAFTER INDICATED _____
PLUGGING CONTRACTOR SPLANE PULLING AND ROUSTABOUT SERVICE LICENSE NUMBER 6372
ADDRESS P.O. BOX 386, CHANUTE, KS 66720
COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 3 MONTH: 6 YEAR: 97
PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL
(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946
WERE: THIS WELL CONSISTED OF A 2" LINER TO APPROX. 800' INSIDE 4 1/2" CASING TO APPROX. 800'. A BOND LOG SHOWED THE 4 1/2" TO BE CEMENTED IN FROM 543.3' TO AT LEAST 30'. THE PLUGGING PROPOSAL WAS TO PART AND REMOVE AS MUCH OF THE 2" AS POSSIBLE AND TO CIRCULATE THE 4 1/2" CASING FULL OF CEMENT.
PLUGGING PROPOSAL RECEIVED BY C.P. TITEL
PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____
OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 3 MONTH: 6 YEAR: 97
ACTUAL PLUGGING REPORT THE 2" LINER WAS SHOT OFF AT 547' AND 547' OF 2" TUBING WAS REMOVED FROM THE WELL. 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 625'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" AT SURFACE. THE 1" PIPE BECAME WEDGED IN THE WELL. 225' OF 1" WAS LEFT-HANDED FROM THE WELL. 400' OF 1" WAS LOST IN THE WELL FROM 625' TO 225'. 94 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.
REMARKS: Control # 19970160-017
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)
I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel
(TECHNICIAN) FORM CP-2/3