

3021289

5-21

TO: API NUMBER 15- _____

STATE CORPORATION COMMISSION SW, SEC. 18, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION 135 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4925 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BARNETT WELL # 11

TECHNICIAN'S PLUGGING REPORT COUNTY ALLEN

OPERATOR LICENSE # _____ WELL TOTAL DEPTH APPROX. 800' FEET

OPERATOR: STATE OF KANSAS CONDUCTOR PIPE: SIZE _____ FEET

NAME AND FEE FUND PLUGGING SURFACE CASING: SIZE 8 FEET N/A

ADDRESS _____

ABANDONED OIL WELL ☒ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR SPLANE PULLING & ROUSTABOUT SERVICE LICENSE NUMBER 6372

ADDRESS P.O. BOX 386, R.R. 4, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 10:00AM DAY: 12 MONTH: 5 YEAR: 97

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROX. 800' CEMENTED IN AT TD ONLY. 780' OF 3/4" SET ON A PACKER WAS IN THIS WELL. 780' OF 3/4" PIPE WAS REMOVED FROM THE WELL. THE PACKER WAS LEFT AT APPROX. 780' IN THE 2" CASING. THE PLUGGING PROPOSAL WAS TO FILL AS MUCH OF THE WELL AS POSSIBLE WITH CEMENT INSIDE AND OUTSIDE THE CASING.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL ☒ PART ☐ NONE ☐


OPERATIONS COMPLETED: HOUR: 11:30AM DAY: 21 MONTH: 5 YEAR: 97

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN INTO THE 2" CASING TO 775'. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 725'. CEMENT WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 3/4" AND 2" ANNULUS AT SURFACE. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" AND 8" ANNULUS AT SURFACE. BOTH THE 3/4" AND 1" LENGTHS OF PIPE WERE REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. 204 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

REMARKS: Control # 19970160-008
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED


(TECHNICIAN)

FORM CP-2/3

RECEIVED
KANSAS CORP COM
1997 MAY 30 AM 11:19