

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21394-00-01
Spot: SWSESE Sec/Twnshp/Rge: 1-10S-20W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: SUTORA Well #: 17
County: ROOKS Total Vertical Depth: 3900 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3783		
PROD	5.5	3899		250 SX
SURF	8.625	242		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2013 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8104

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500# hulls.
Port Collar at 1685' w/400 sx cement.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2013 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3648' and pumped 125 sx cement w/225 # hulls.
Pulled tubing to 2445' and pumped 125 sx cement w/225 # hulls.
Pulled tubing to 1234' and pumped 165 sx cement.
Cement circulated to pit.
POOH. Hooked to braden head and pumped 10 sx cement at 150 psi. Shut in.
Topped off casing with 20 sx cement. Casing stayed full.

GPS: 39.20594 -099.49685

Perfs:

Top	Bot	Thru	Comments
3772	3774		
3766	3768		
3758	3760		

Remarks: SWIFT WELL SERVICE TICKET # 24431

Plugged through: TBG

KCC WICHITA

JUN 19 2013

RECEIVED

District: 04

Signed Ray A Dinkel (TECHNICIAN)

CM