

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20688-00-01
Spot: NWSWNESW Sec/Twnshp/Rge: 29-34S-30W
1964 feet from S Section Line, 3934 feet from E Section Line
Lease Name: ADAMS Well #: 1-29
County: MEADE Total Vertical Depth: 5980 feet

Operator License No.: 5225
Op Name: QUINQUE OPERATING COMPANY
Address: 908 NW 71ST ST
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4300		WITH 10 SX CMT
COND	20	40		
PROD	4.5	5977	2500	WITH 410 SX CMT
SURF	8.625	1533		WITH 500 SX CMT

Well Type: EOR UIC Docket No: E26189.1 Date/Time to Plug: 05/23/2013 9:00 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.
Proposal Rcvd. from: PHIL DOLLAR Company: PHIL DOLLAR OILFIELD SERVICE Phone: (806) 435-3373

Proposed Plugging Method: Pump 40 bbls mud down 4 1/2" csg. Set CIBP @ 4300'. Pump 10 sx cmt on top. Load hole w/mud. Shoot 4 1/2" @ 2500'. Lay down same. TIH w/tubing. Pump 50 sx @ 1560'. TOH. Pump 25 sx @ 400', 15 sx from 60' to Surface.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2013 10:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

BRIDGE PLUG @ 5600'. SET CIBP @ 4300' WITH 10 SX CMT. LOADED HOLE WITH 25 SX GEL. 1ST PLUG AT 1571' WITH 50 SX CMT. 2ND PLUG AT 408' WITH 25 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5785	5789		
4361	4366		

KCC WICHITA
JUN 10 2013
RECEIVED

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY PHIL DOLLARD OILFIELD SERVICES.

Plugged through: TBG

District: 01

RECEIVED

JUN - 4 2013

KCC DODGE CITY

Signed



(TECHNICIAN)

cc to WIC 6/11/13
6/20/13

