

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-22022-00-00

Spot: NWNESWSE

Sec/Twnshp/Rge: 32-16S-19W

993 feet from S Section Line, 1882 feet from E Section Line

Lease Name: LITTLER

Well #: 7

County: RUSH

Total Vertical Depth: 3813 feet

Operator License No.: 32500

Op Name: T & P OIL & GAS, L.L.C.

Address: 9010 PINE STREET
LENEXA, KS 66220

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 1329 | | WITH 550 SX CMT |

Well Type: DH

UIC Docket No:

Date/Time to Plug: 05/08/2013 12:45 AM

Plug Co. License No.: 5184

Plug Co. Name: SHIELDS OIL PRODUCERS INC.

Proposal Rcvd. from: TOM PANGEL

Company: SHIELDS OIL PRODUCERS INC.

Phone: (785) 483-3141

Proposed Plugging Method: 1ST PLUG AT 3763' WITH 50 SX CMT. 2ND PLUG AT 1320' WITH 50 SX CMT. 3RD PLUG AT 510' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN

WitnessType: NONE

Date/Time Plugging Completed: 05/08/2013 2:45 AM

KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 3763' WITH 50 SX CMT. 2ND PLUG AT 1320' WITH 50 SX CMT. 3RD PLUG AT 510' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY SOS.

Plugged through: DP

KCC WICHITA

JUN 10 2013

RECEIVED

District: 01

Signed

(TECHNICIAN)

RECEIVED

JUN - 4 2013

KCC DODGE CITY