

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25834-00-00  
Spot: NESWSNE Sec/Twnshp/Rge: 5-15S-19W  
1996 feet from N Section Line, 2299 feet from E Section Line  
Lease Name: WINNIE Well #: 1-5  
County: ELLIS Total Vertical Depth: 3698 feet

Operator License No.: 4787  
Op Name: TDL, INC.  
Address: 1310 BISON RD  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1315		200 SX CMT
PROD	5.25	3692		150 SX
SURF	8.875	207		150 SX
TI	2.875	3694		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/06/2013 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: BRETT HILDEBRAND Company: TDL, INC. Phone: (785) 871-7311

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.  
Open hole from 3692'-3698'.DV @ 1315' with 200 sacks. Cement did circulate.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/06/2013 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 3500' and pumped 13 sx gel followed by 50 sx cement w/100 # hulls.  
Pulled tubing to 1650' and pumped 200 sx cement.  
Cement circulated.  
POOH. Hooked to casing and pumped 35 sx cement at 350 psi. Shut in.  
Hooked to braden head and pumped 5 sx cement at 100 psi.

GPS: 38.77826 -099.45672

Remarks: SOS CEMENTING TICKET # 1033

Plugged through: TBG

KCC WICHITA

JUN 19 2013

RECEIVED

District: 04

Signed

Ray A Dinkel  
7/02/13

(TECHNICIAN)

CM

JUN 10 2013