

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-22438-00-00  
Spot: W2NWSWNW Sec/Twnshp/Rge: 16-18S-27W  
1650 feet from N Section Line, 100 feet from W Section Line  
Lease Name: STANLEY-HINEMAN Well #: 1-16  
County: LANE Total Vertical Depth: 4680 feet

Operator License No.: 4629  
Op Name: BRITO OIL COMPANY, INC.  
Address: 1700 N WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	255		WITH 175 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/28/2013 2:00 AM  
Plug Co. License No.: 6039 Plug Co. Name: L. D. DRILLING, INC.  
Proposal Rcvd. from: DAVE YOTT Company: L. D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: 1ST PLUG AT 2120' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 05/28/2013 5:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2120' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

KCC WICHITA

JUN 10 2013

RECEIVED

District: 01

Signed Michael Maier  
6/24/13 (TECHNICIAN)

RECEIVED

JUN - 4 2013

KCC DODGE CITY

*Handwritten signature*