

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-20637-00-00  
Spot: NWSESESW Sec/Twnshp/Rge: 10-14S-17W  
339 feet from S Section Line, 3201 feet from E Section Line  
Lease Name: CHRISTINA A Well #: 4  
County: ELLIS Total Vertical Depth: 3576 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3562		75 SX
SURF	8.625	167		130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/03/2013 9:30 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: CURTIS GABEL Company: BEREXCO LLC Phone: (785) 623-0546

Proposed Plugging Method: Ordered 420 sx 60/40 pozmix 4% gel cement, 1/4 # Flo-Cele per sx and 500 # hulls.  
Perforations: 638', 1197' and 1650'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/03/2013 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3562' and pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 2519' and pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 1518' and pumped 170 sx cement.  
Cement circulated to pit.  
POOH. Hooked up to casing and pumped 15 sx cement at 350 psi. Shut in.  
Hooked to braden head and pumped 15 sx cement at 200 psi.  
GPS: 38.84319 -099.19926

Perfs:

Remarks: ALLIED CEMENTING TICKET # 56612

Plugged through: TBG

KCC WICHITA  
JUN 12 2013  
RECEIVED

District: 04

Signed

Ray A Dinkel  
6/19/13 (TECHNICIAN)

cm

JUN 04 2013