

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-21595-00-00  
Spot: NENW Sec/Twnshp/Rge: 27-33S-35W  
4649 feet from S Section Line, 3322 feet from E Section Line  
Lease Name: HILBIG Well #: 1-27  
County: STEVENS Total Vertical Depth: 6500 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6000		WITH 2 SX CMT
COND	20	40		WITH 150 SX CMT
PROD	4.5	6499	0	WITH 780 SX CMT
SURF	8.625	1600		WITH 715 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/06/2013 9:30 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: GREG KLAUS Company: BEREXCO LLC Phone: (316) 772-8650

Proposed Plugging Method: SET CIBP @ 6000' WITH 2 SX CMT. PERFORATE @ 1540' WITH 50 SX CMT. PERFORATE @ 600' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/06/2013 2:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 6000' WITH 2 SX CMT. PERFORATE @ 1500' WITH 50 SX CMT.  
PERFORATE @ 600' WITH 140 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6033	6040		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

KCC WICHITA

JUN 10 2013

RECEIVED

District: 01

RECEIVED

Signed

*[Signature]*  
6/11/13 (TECHNICIAN)

JUN -7 2013 RECEIVED

KCC DODGE CITY JUN -7 2013

KCC DODGE CITY