

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03592-00-00
Spot: W2W2SWNW Sec/Twnshp/Rge: 3-9S-16W
3300 feet from S Section Line, 5230 feet from E Section Line
Lease Name: GAMBLE Well #: 4
County: ROOKS Total Vertical Depth: 3422 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	1238		
PROD	5.5	3422		140 SX
SURF	8.625	74		40 SX
T1	2	3000		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT, INC. Phone: (620) 793-5100

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement and 400 # hulls.
Well had parted tubing at 1340'. Tried washover pipe and overshot with no luck. Tubing appeared to be swiss cheese.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/09/2013 10:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 200', 775' and 1280'.
Ran tubing to 1214' and pumped 100 sx cement to circulate 4 1/2" casing to surface.
Shut in 4 1/2" casing and pumped 50 sx cement to circulate between 4 1/2" and 5 1/2" casing.
Pulled out tubing. Hooked to 4 1/2" casing and pumped 50 sx cement. Maximum pressure 400 psi.
Hooked to 8 5/8" x 5 1/2" annulus and pumped 5 sx cement. Pressured to 200 psi.
GPS: 39.30266N -099.10294W

Perfs:

Top	Bot	Thru	Comments
3020	3350		

Remarks: COPELAND ACID AND CEMENT TICKET # 38452

Plugged through: TBG

KCC WICHITA
JUN 06 2013
RECEIVED

District: 04

Signed Pat Bedore
6/24/13 (TECHNICIAN)

CM

JUN 03 2013