

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-00848-00-00  
Spot: W2NWNWNE Sec/Twnshp/Rge: 1-31S-9W  
4513 feet from S Section Line, 2340 feet from E Section Line  
Lease Name: CONRARDY B OWWO Well #: 1-1  
County: HARPER Total Vertical Depth: 4513 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6200 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4513	2380	150 SX
SURF	8.625	412		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/24/2013 5:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: \_\_\_\_\_ Phone: (620) 277-0806

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/24/2013 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

5/24/13, SET CIBP @ 4330', CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2380' PULLED CASING TO 1517' SPOTTED 35 SX CEMENT. PULLED CASING TO 1014' SPOTTED 35 SX CEMENT. PULLED CASING TO 416' CIRCULATED TO SURFACE WITH 165 SX CEMENT. CHECKED TOP PLUG 5/28/2013, FELL BACK 45' FILLED WITH 10 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4436	4445		
4428	4432		
4422	4426		
4386	4406		

Remarks: ALLIED CEMENTING OUT OF MEDICINE LODGE - TICKET #59533, PAST TEN YEAR TA.

Plugged through: CSG

District: 02

Signed

KCC WICHITA

JUN 20 2013

RECEIVED

[Signature]  
(TECHNICIAN)  
6/21/13