

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25430-00-00  
Spot: N2SWSWNE Sec/Twnshp/Rge: 4-19S-15W  
2210 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: MAURICE Well #: 1-4  
County: BARTON Total Vertical Depth: 3630 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2099		155 SX
SURF	8.625	1011		400 SX
T1	2.375	1900		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/16/2013 9:00 AM  
Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/16/2013 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500' and 1000'.  
Ran tubing to 2000' and pumped 100 sx cement w/100 # hulls.  
Pulled tubing to 1000' and pumped 50 sx cement w/100 # hulls.  
Pulled tubing to 500'. Circulated cement to surface with 60 sx cement.  
Circulated cement to surface on surface pipe with 100 sx cement.  
Pulled tubing. Topped off with 10 sx cement.

GPS: 38.42856 -098.98582

Perfs:

Top	Bot	Thru	Comments
1856	1866		
1838	1848		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSGTB6

KCC WICHITA

JUN 05 2013

RECEIVED

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

cm

6/26/13

Rec'd 6/3 2013