

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23747-00-00
Spot: N2NW Sec/Twnshp/Rge: 17-18S-15W
4620 feet from S Section Line, 3960 feet from E Section Line
Lease Name: SCHNEIDER Well #: 1
County: BARTON Total Vertical Depth: 3580 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3575	2000	350 SX
SURF	8.625	985		450 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/15/2013 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMANN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/15/2013 6:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut casing at 2000'.
Pulled casing to 1500' and pumped 150 sx cement w/200 # hulls.
Pulled casing to 950' and pumped 50 sx cement w/100 # hulls.
Pulled casing to 500'. Circulated cement to surface with 110 sx cement and 200 # hulls.
Pulled casing. Hole stayed full.

GPS: 38.49098 -099.00962

Perfs:

Top	Bot	Thru	Comments
3268	3273		
3255	3258		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

KCC WICHITA

JUN 05 2013

RECEIVED

District: 04

Signed Bruce Rodie
6/26/13 (TECHNICIAN) cm

MAY 23 2013