

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-20535-00-01  
Spot: NESESESE Sec/Twnshp/Rge: 19-22S-3W  
392 feet from S Section Line, 176 feet from E Section Line  
Lease Name: BARTEL Well #: 2  
County: HARVEY Total Vertical Depth: 3900 feet

Operator License No.: 6804  
Op Name: LACHENMAYR OIL LLC  
Address: PO BOX 526  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3270		
PROD	4.5	3700		725 SX
SURF	8.625	294		200 SX

Well Type: SWD UIC Docket No: D21076.0 Date/Time to Plug: 03/28/2013 12:00 AM  
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC  
Proposal Rcvd. from: JAY SCOTT Company: Phone:

Proposed Plugging Method: Per KCC instructions. We will not try to recover any casing. 6/5/1987 1" pipe ran to 55' and circulated cement to surface 28 sacks

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/28/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

3200' SPOTTED 25 SX COMMON CEMENT -- 4% CC -- TAGGED TOC @ 2966'.  
PULLED TUBING TO 2063' SPOTTED 25 SX CEMENT COMMON 4% CC, TAGGED TOC @ 1830'. WIRELINE SHOT 4 SHOT CLUSTER @ 550' & 300'. PRESSURED TO 400 LBS HELD, FILLED CASING FROM 558' TO SURFACE WITH 62 SX OF COMMON CEMENT. 4/17/13 CUT BRADEN HEAD OFF, BACKSIDE FILLED TO TOP OF CASING WITH CEMENT FROM PRIOR SQUEEZE JOB.

Perfs:

Top	Bot	Thru	Comments
3192	3193		

**KCC WICHITA**  
**JUN 07 2013**  
**RECEIVED**

Remarks: CONSOLIDATED OUT OF EL DORADO--COMMON CEMENT USED--TICKET #38532. PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 02

Signed BJ Hope  
(TECHNICIAN)

✓  
✓  
✓  
6/26/13  
✓