

\* OK TO INV. AS PLUG DT'S.  
W/IN 5 YR. CUTOFF.

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-131-20215-00-00  
Spot: S2NENENW Sec/Twnshp/Rge: 4-3S-13E  
600 feet from N Section Line, 2310 feet from W Section Line  
Lease Name: D & K HEINEN Well #: 1-4  
County: NEMAHA Total Vertical Depth: 1133 feet

Operator License No.: 31439  
Op Name: KINNEY OIL COMPANY  
Address: 1401 17TH ST STE 870  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	265		170 sx cement

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/13/2010 12:00 AM  
Plug Co. License No.: 30141 Plug Co. Name: SUMMIT DRILLING COMPANY  
Proposal Rcvd. from: DAN COX Company: SUMMIT DRILLING COMPANY Phone: (620) 344-1465

Proposed Plugging Method: 50' PLUG AT BOTTOM, 50' PLUG AT PRODUCING FORMATIONS, 50' PLUG AT KC, 300' TO SURFACE.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE  
Date/Time Plugging Completed: 12/13/2010 3:50 AM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

HAD THE DRILL PIPE RAN TO 1132' AND PUMPED 15 SACKS OF CEMENT. PULLED THE PIPE UP TO 910' AND PUMPED 15 SACKS OF CEMENT. PULLED THE PIPE UP TO 600' AND PUMPED 15 SACKS OF CEMENT. PULLED THE PIPE UP TO 300' AND PUMPED 105 SACKS OF CEMENT TO THE SURFACE.

Perfs:

RECEIVED  
JUN 27 2013  
KCC Chanute Dist #3  
TH

Remarks:

Plugged through: DP

District: 03

Signed Taylor C. Herman  
3/10/13 (TECHNICIAN)

KCC WICHITA Form CP-2/3

JUL 01 2013

RECEIVED