

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-073-23224-00-00  
Spot: SESENE Sec/Twnshp/Rge: 5-22S-11E  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease Name: CURRY MARY Well #: 1  
County: GREENWOOD Total Vertical Depth: 1950 feet

Operator License No.: 6470  
Op Name: SCHANKIE WELL SERVICE, INC.  
Address: PO BOX 397  
MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1937		75 SX
SURF	8.625	103		58 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2013 8:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: CLIFF SCHANKIE Company: \_\_\_\_\_ Phone: (620) 437-2595

Proposed Plugging Method: Spot cement plug down 2 3/8" tubing 15sk @1773', gel spacer, perforate 2 shots @800', spot cement plug 15sk @800', gel spacer, perforate 2 shots @150', spot cement plug 55sk @160' to surface

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/21/2013 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

tubing stuck in well, shot tubing @ 1790' & 1758' squeezed 30 sx cement, shot tubing off @ 1200', perfed well @ 800' & 150', ran tubing to 800' pumped 25 sxs cement, pulled tubing to 160' pumped 63 sxs cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1823	1893		

RECEIVED

JUL 01 2013

KCC Chanute Dist. #3

MH

KCC WICHITA

Remarks:

JUL 03 2013

Plugged through: TBG

RECEIVED

District: 03

Signed Mike Heffern  
7/03/13 (TECHNICIAN)