

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21724-00-00
Spot: NESESESW Sec/Twnshp/Rge: 5-22S-16W
358 feet from S Section Line, 2454 feet from W Section Line
Lease Name: M & M UNIT Well #: 1-5
County: PAWNEE Total Vertical Depth: 3975 feet

Operator License No.: 31725
Op Name: SHELBY RESOURCES LLC
Address: 445 UNION BOULEVARD SUITE 208
LAKEWOOD, CO 80228

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 1017 | | WITH 450 SX CMT |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/16/2013 7:45 PM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: ALAN LOFTIS Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 3874' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 50 SX CMT. 3RD PLUG AT 310' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: NONE
Date/Time Plugging Completed: 06/16/2013 9:45 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

1ST PLUG AT 3874' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 50 SX CMT. 3RD PLUG AT 310' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

KCC WICHITA

JUL 01 2013

RECEIVED

District: 01

RECEIVED
JUN 25 2013
KCC DODGE CITY

Signed

Nathan Willis
7/03/13
(TECHNICIAN)