

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22259-01-00  
Spot: E2NENWNE Sec/Twnshp/Rge: 30-30S-5W  
330 feet from N Section Line, 1325 feet from E Section Line  
Lease Name: RHOADS 93 FAMILY TRUST 3 Well #: 30-1H  
County: KINGMAN Total Vertical Depth: 60 feet

Operator License No.: 34574  
Op Name: SHELL GULF OF MEXICO INC.  
Address: 150 N DAIRY-ASHFORD (77079) PO BO  
HOUSTON, TX 77001

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	18	60		42 SX
PROD	0	0		0 SX
SURF	0	0		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2013 12:00 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Revd. from: WILLARD LEVY Company: \_\_\_\_\_ Phone: (620) 896-1412

Proposed Plugging Method: 1. Check Total Depth of conductor/mouse hole. (Document) 2. Check for static water level. (Document) 3. Cut conductor/ mouse pipe off 5' below surface. 4. Set trim pipe to bottom of hole pump Type H cement until full. 5. Return next day check for settling top it off if needed. 6. Weld cap on pipe and weep hole.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/17/2013 12:00 AM KCC Agent: JEFF KLOCK

Actual Plugging Report:

Perfs:

1. DOCUMENTED TOTAL DEPTH OF CONDUCTOR AT 48' AND MOUSE HOLE AT 48'. 2. DOCUMENTED STATIC WATER LEVEL AT 3' FOR CONDUCTOR AND 2' FOR MOUSE HOLE. 3. CUT CONDUCTOR/MOUSE PIPE OFF 5' BELOW SURFACE. 4. PUMPED 48 SACKS FOR CONDUCTOR AND 28 SACKS FOR MOUSE HOLE OF TYPE H CEMENT UNTIL FULL. 5. RETURNED NEXT DAY, CHECKED FOR SETTLING, TOP OFF NOT NEEDED. 6. WELDED CAP ON PIPE AND WEEP HOLE.

Remarks:

*\* CONDUCTOR ONLY PER PERMS*

Plugged through: CSG

KCC WICHITA

JUL 02 2013

RECEIVED

District: 02

Signed

*Jeff Klock*  
7/03/13 (TECHNICIAN)