

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-22025-00-00
Spot: SWNENWNE Sec/Twnshp/Rge: 11-19S-20W
450 feet from N Section Line, 1900 feet from E Section Line
Lease Name: COMBS Well #: 1
County: RUSH Total Vertical Depth: 4179 feet

Operator License No.: 30458

Op Name: RJM COMPANY

Address: PO BOX 256
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	221		WITH 150 SX CMT

Well Type: DH

UIC Docket No:

Date/Time to Plug: 06/17/2013 7:45 AM

Plug Co. License No.: 33350

Plug Co. Name: SOUTHWIND DRILLING, INC.

Proposal Rcvd. from: BILL SANDERS

Company: SOUTHWIND DRILLING, INC.

Phone: (620) 564-3800

Proposed Plugging Method: 1ST PLUG AT 1440' WITH 50 SX CMT. 2ND PLUG AT 510' WITH 50 SX CMT. 3RD PLUG AT 250' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS

WitnessType: NONE

Date/Time Plugging Completed: 06/17/2013 9:45 AM

KCC Agent: NATHAN WILLIS

Actual Plugging Report:

Perfs:

1ST PLUG AT 1440' WITH 50 SX CMT. 2ND PLUG AT 510' WITH 50 SX CMT. 3RD PLUG AT 250' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY.

Plugged through: DP

KCC WICHITA

JUL 01 2013

RECEIVED

District: 01

Signed

Nathan Willis

V. Davis

(TECHNICIAN)

RECEIVED

JUN 25 2013

KCC DODGE CITY