

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21950-00-00
Spot: S2NESW Sec/Twnshp/Rge: 27-16S-28W
1628 feet from S Section Line, 3284 feet from E Section Line
Lease Name: FULLMER Well #: 2
County: LANE Total Vertical Depth: 4618 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PC	4.5	2186		CEMENTED TO 0
PROD	4.5	4603	0	WITH 200 SX CMT
SURF	8.625	219		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2013 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT INC Phone: (620) 793-0102

Proposed Plugging Method: PUMP 30 SX CMT WITH 200# HULLS. GEL SPACER TO 2300'. PUMP 150 SX CMT FROM 2300' TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/20/2013 9:00 AM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

PUMPED DOWN 4 1/2" WITH 30 SX CMT W/200# HULLS -10 SX GEL - 150 SX CMT.
PRESSURED 8 5/8" X 4 1/2" ANNULUS TO 200 PSI WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4216	4223		

Remarks: USED 60/40 POZMIX 4% GEL SWIFT SERVICES.

Plugged through: CSG

KCC WICHITA
JUL 01 2013
RECEIVED

District: 01

RECEIVED
JUN 25 2013
KCC DODGE CITY

Signed Nathan Willis
7/03/13 (TECHNICIAN)

AWT