

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-22862-00-01
Spot: S2SESE Sec/Twnshp/Rge: 1-25S-19E
240 feet from S Section Line, 720 feet from E Section Line
Lease Name: MCFADDEN Well #: W 4
County: ALLEN Total Vertical Depth: 900 feet

Operator License No.: 34772
Op Name: ENSMINGER ENERGY LLC
Address: 1446 3000 ST.
MORAN, KS 66755

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	869		
SURF	6.25	25		

Well Type: EOR UIC Docket No: E18507.27 Date/Time to Plug:
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: Run 1" pipe to TD. Circulate cement from TD to surface.

Plugging Proposal Received By: RYAN DULING WitnessType: NONE
Date/Time Plugging Completed: 06/25/2013 10:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe to 850' inside 2.875" casing. The 2.875" casing was cemented inside 6.25" surface casing. Circulated cement through the 1" pipe inside the 2.875" casing from TD to surface. Pulled 1" pipe and topped well off with cement. A total of 30 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
JUN 27 2013
KCC Chanute Dist. #3

RD

KCC WICHITA
JUL 01 2013

Remarks: PLUGGED DUE TO A FAILED MIT.

Plugged through: CSG

RECEIVED

District: 03

Signed [Signature]
(TECHNICIAN)

cc to MC 7/02/13
7/03/13