

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21277-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 25-17S-10W
2258 feet from S Section Line, 2277 feet from E Section Line
Lease Name: DOHRMAN Well #: 1
County: ELLSWORTH Total Vertical Depth: 3500 feet

Operator License No.: 34674
Op Name: H & D EXPLORATION LLC
Address: 165 WEST 1ST PO BOX 387
HOISINGTON, KS 67544

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3319 | | 150 SX |
| SURF | 8.625 | 273 | | 170 SX |
| SURF | 8.62 | 2725 | | 170 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/20/2013 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JIM LYMAN Company: DS & W WELL SERVICING, INC. Phone: (620) 786-4258

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 06/20/2013 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, CK BOTTOM. SAND PERFS TO 3150' AND CAP WITH 5 SX'S SAND. SHOOT CASING OFF AT 2000' AND PULL TO 1250' AND PUMP 20 SX'S GEL FOLLOWED BY 35 SX'S CEMENT. PULL CASING TO 900' AND PUMP 35 SX'S CEMENT. PULL CASING TO 320' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF. USED 245 SX'S CEMENT.

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-38595. LOG TECH OF KS. #7514.

Plugged through: CSG

KCC WICHITA
JUL 02 2013
RECEIVED

District: 02

Signed Virgil Clothier
7/03/13 (TECHNICIAN)