

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-073-21061-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 33-23S-11E  
990 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: CARSON C Well #: 1  
County: GREENWOOD Total Vertical Depth: 2440 feet

Operator License No.: 6470  
Op Name: SCHANKIE WELL SERVICE, INC.  
Address: PO BOX 397  
MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2436		50 SX
SURF	7	61		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/24/2013 8:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: CLIFF SCHANKIE Company: \_\_\_\_\_ Phone: (620) 437-2595

Proposed Plugging Method: Filled with rock and one sack cement cap 2300 ft; gel spacer, perforate 2 shots @800 ft, spot cement plug 15sk @800 ft, gel spacer, perforate 2 shots @150 ft, spot cement plug 55sk @160 ft to surface

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/24/2013 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1800' pumped 15 sxs cement, shot casing @ 800' & 150' pumped 25 sxs cement @ 800' pulled tubing to 150' circ. Cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2436	2440		

RECEIVED

JUL 01 2013

Chanute Dist #3

MH

KCC WICHITA

JUL 03 2013

RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed Mike Wall  
7/03/13 (TECHNICIAN)