

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20356-00-00  
Spot: SESW Sec/Twnshp/Rge: 20-33S-34W  
722 feet from S Section Line, 1992 feet from W Section Line  
Lease Name: SHUCK A Well #: 2  
County: SEWARD Total Vertical Depth: 6357 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6225		WITH 5 SX CMT
PROD	5.5	6355	1718	WITH 130 SX CMT
SURF	8.625	1679		WITH 800 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/18/2013 1:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: SET CIBP @ 6225' WITH 5 SX CMT. PLUG AT 1710' WITH 20 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/18/2013 5:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 6225' WITH 5 SX CMT. 1ST PLUG AT 1712' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 592' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6274	6288		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND

Plugged through: CSG

KCC WICHITA

JUL 01 2013

RECEIVED

District: 01

RECEIVED

JUN 25 2013

KCC DODGE CITY

Signed

(TECHNICIAN)