

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22817-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 28-15S-13W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: KEIL A Well #: 1
County: RUSSELL Total Vertical Depth: 3341 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S MAIN ST
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3337		100 SX
SURF	8.625	400		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/31/2013 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: MESSENGER PETROLEUM Phone: (620) 727-3409

Proposed Plugging Method: Ordered 270 sx 60/40 pozmix 4% gel cement w/500 # hulls.
10 joints of 2.375" tubing left in hole

Plugging Proposal Received By: CASE MORRIS WitnessType: PARTIAL
Date/Time Plugging Completed: 05/31/2013 8:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

05/24/2013- Rigged up and down 8 joints using tubing thongs to turn tubing. Shut down.
05/30 And 05/31/2013- Ran drill bit in using a power swivel and got down to 600'. Bit hung up. Pulled out of well with trouble and pulled out a bent joint. Ran in with open end and worked it down to 775'. Pumped 175 sx cement w/400 # hulls. Cement circulated to surface. Tried to pull out and tubing hung up leaving 10 joints of tubing in well.
POOH. Hooked to casing and pumped 20 sx cement at 150 psi. Shut in.
Hooked up to braden head and pumped 50 sx cement at 300 psi. Shut in.
GPS: 38.71957 -098.78094

Remarks: QUALITY WELL SERVICES TICKET # 5941

Plugged through: TBG

KCC WICHITA

JUN 19 2013

RECEIVED

District: 04

Signed

Ray Dinkel
6/20/13

(TECHNICIAN)

cm

JUN 11 2013