

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20218-00-00
Spot: SWNWNEW Sec/Twnshp/Rge: 27-20S-35W
340 feet from N Section Line, 1620 feet from W Section Line
Lease Name: EDER Well #: 1-27
County: WICHITA Total Vertical Depth: 5150 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	267		WITH 200 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/05/2013 9:00 AM

Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC

Proposal Rcvd. from: CARLOS FIBELA Company: H2 DRILLING LLC Phone: (316) 636-2090

Proposed Plugging Method: 1ST PLUG AT 2320' WITH 50 SX CMT. 2ND PLUG AT 1140' WITH 80 SX CMT. 3RD PLUG AT 550' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 05/05/2013 11:00 AM

WitnessType: NONE
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2320' WITH 50 SX CMT. 2ND PLUG AT 1140' WITH 80 SX CMT. 3RD PLUG AT 550' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

KCC WICHITA

JUN 10 2013

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed

Michael Maier
6/26/13
(TECHNICIAN)

RECEIVED

JUN - 3 2013

KCC DODGE CITY

AMW