

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20952-00-00
Spot: E2W2NE Sec/Twnshp/Rge: 5-16S-31W
1260 feet from N Section Line, 1735 feet from E Section Line
Lease Name: HELL CREEK 5A Well #: 1
County: SCOTT Total Vertical Depth: 4622 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220		WITH 170 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/08/2013 9:30 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: MARK BIGGE Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2260' WITH 50 SX CMT. 2ND PLUG AT 1600' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 06/08/2013 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2260' WITH 50 SX CMT. 2ND PLUG AT 1600' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

KCC WICHITA

JUN 17 2013

RECEIVED

District: 01

Signed Stephen J. Pfeifer
6/20/13 (TECHNICIAN)

RECEIVED

JUN 10 2013

KCC DODGE CITY

Handwritten initials