

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22511-00-00
Spot: SENE SW Sec/Twnshp/Rge: 1-6S-23W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: JOHN KEMPER Well #: 2
County: GRAHAM Total Vertical Depth: 3790 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3785		125 SX
SURF	8.675	265		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2013 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: THOMAS ATKINS Company: ALLIANCE WELL SERVICE INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Perforations at 3718' to 3722'.
Port Collar at 1988' w/550 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2013 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3500' and pumped 125 sx cement w/200 # hulls.
Pulled tubing to 1900' and pumped 175 sx cement w/200 # hulls. Good circulation of cement.
Pulled tubing out. Topped off w/30 sx cement. Hole standing full.
Tied on to backside and squeezed with 10 sx cement. Shut in pressure 500 psi.

GPS: 39.55809 -099.83642

Perfs:

Top	Bot	Thru	Comments
3718	3722		

Remarks: CONSOLIDATED CEMENT TICKET # 39942

Plugged through: TBG

KCC WICHITA
JUN 12 2013
RECEIVED

District: 04

Signed Mary Mills
6/12/13 (TECHNICIAN)

CM

JUN 07 2013